

1-040822

1-12

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 151-20,738

C NE NE /4 SEC. 19, 28 S, 13 W
4620 feet from S section line
660 feet from E section line

Operator license# 5893 Lease Eubank well # 1

Operator: Pratt Well Service, Inc. County Pratt

Address: P.O. Box 847 Well total depth 3200 feet
Pratt, KS 67124 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 256 feet

104.00

Aband. oil well , Gas well X, Input well , SWD , D & A

Plugging contractor: Pratt Well Service, Inc. License# 5893

Address: P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 12 Month: January Year: 1994

Plugging proposal received from: Kenny Gates

Company: Pratt Well Service, Inc. Phone: 316-672-2531

Were: 4 1/2" at 3091' w/125 sx cement, Perfs at 2905-15'
1st plug sand back to 2800' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx
cement, 10 sx gel, 100 lbs. hulls, and 150 sx cement.

Plugging Proposal Received by: Duane Rankin
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:30 am, Day: 12, Month: January, Year: 1994

Actual plugging report: 1st plug sanded back to 2800' and dumped 4 sx cement on
top of sand bridge through bailer,
2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx
cement, 10 sx gel, 100 lbs. hulls and 150 sx cement.

Maximum pressure 500 psi and shut in 200 psi.
Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1900' of 4 1/2" casing.

I did[X] / did not[] observe the plugging.

Stephen J. Pfeiffer
(agent)
RECEIVED
STATE CORPORATION COM.
JAN 20 1994

Form CP-2/3
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 1-28-94
INV. NO. 39827