

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-20904-0000

R

C-S-E-NW, Sec. 19, T 28 S, R 13 W/D

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Lemon Well # 1-19

Operator: Tejas Energies Inc.
Name & Address P.O. Box 947
Pratt Kansas
67124

County Pratt

Well Total Depth 4640 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 285'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176 Chase, Kansas 67524

Company to plug at: Hour: 9:00AM Day: 6 Month: 10 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Jack Cambell

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2 @ 4233' Perf. 3971' to 75' 1st plug sanded bottom back to 3900' & 5 sbx cement on top of sand, 2nd plug pumped through head on 8 5/8" w/ 10 sbx gell 3 sbx hulls & 10 sbx gell & 50 sbx cement & 1 hull & 25 sbx gell & release rubber plug, follow it w/ 150 sbx cement. They recovered 3235' of 4 1/2" pipe.

Signed Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 11:00AM Day: 6 Month: 10 Year: 19 82

ACTUAL PLUGGING REPORT 1st plug sanded bottom back to 3900' & dumped 5 sbx cement on top of sand through bailer, 2nd plug pumped through head on 8 5/8". 3 sbx hulls & 10 sbx gell & 50 sbx cement & 1 sbx hull & 25 sbx gell & released rubber plug & followed it with 150 sbx cement. The cementing was accomplished by Allied Cementing. Max pump pressure was 400# shut in at 200#

Remarks: Mr. J. H. Metz saw top plug pumped.

RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1982
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as hereinafter stated and that I (did / did not) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED
DATE 10-25-82
INV. NO. 1465-W