

12-29-87 15-151-21034-000

API NUMBER 15-151-21,034

To: 1040033  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE NE, SEC. 20, T 28 S, R 13 W/EX

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Letholt Well # 1-20

Operator: Texas Energies, Inc.

County Pratt 15/1

Name & Address Box 947

Well Total Depth 4646 feet

Pratt, KS 67124

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 29 Month: 12 Year: 19 87

Plugging proposal received from Ted Moff

(company name) Kelso Casing Pulling (phone) 316-672-7838

were: 4 1/2" at 4645' PBD 4412' Perfs at 4348-56, 4418-21' Elevation 1961' GL

1st plug sand back to 4370' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 29 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4370' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
JAN 06 1988  
1-06-88  
WICHITA, KANSAS

Maximum pressure 1000 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2600' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

DATE 1-11-88

INV. NO. 19514