

1 050674

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,738-0000

N/2 SW, SEC. 20, T 28 S, R 130 W/E

1800 feet from S section line

4060 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4606

Lease Name Joann Ryan Well # 1

Operator: Texas Crude Exploration, Inc County Pratt 149.50

Name & Address 2100 Texas Crude Bldg. Well Total Depth 4600 feet

801 Travis Conductor Pipe: Size _____ feet

Houston, Texas 77002 Surface Casing: Size 8 5/8" feet 260

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company License Number 5929

Address 205 E Cental Suite 120 Wichita KS 67202

Company to plug at: Hour: 1:00pm Day: 12 Month: November Year: 1985

Plugging proposal received from Irvin Neighbors

(company name) Duke Drilling Company (phone) 316-793-8366

were: To keep hole full of heavy mud + spot cement plugs through drill pipe. 1st plug @ base of th Anhydrite with 50sx. 2nd plug 30' below base of surface pipe with 40sx. 3rd plug @ 40' with solid bridge plug + 10sx of cement. Circulate rathole w/ 15sx

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30pm Day: 12 Month: November Year: 1985

ACTUAL PLUGGING REPORT Kept hole full of heavy mud + spotted plugs through drill pipe. 1st plug @ 810' w/ 50sx cement 2nd plug @ 290' w/ 40sx cement 3rd plug @ 40' w/ SBP + 10sx cement circulated Rathole with 15sx cement

Anhydrite (795'-810') Elevation 1958 GL

Remarks: Allied pumped 60/40 pozmix 6% gel cement
(if additional description is necessary, use BACK of this form.)

INVOICED
NOV 22 1985

RECEIVED
OBSERVE THIS PLUGGING.
STATE CORPORATION COMMISSION

Signed Richard W. Lacey
(TECHNICIAN)

DATE _____

NOV 18 1985

INV. NO. 11160