

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

3-13

2-040875

15-077-20998-00-00

API NUMBER: 15-077-02-998

SW NW NE, SECTION 35 TOWNSHIP 31 RANGE 9W

OPERATOR LICENSE # 31532 4290 FEET FROM S SECTION LINE
OPERATOR BISON PRODUCTION COMPANY 2310 FEET FROM E SECTION LINE
NAME & 9320 EAST CENTRAL
ADDRESS WICHITA, KS 67206
LEASE NAME: NEWBERRY #3
COUNTY: HARPER 143.49
WELL TOTAL DEPTH: 4415'
PIPE: _____
SURFACE CASING: 8 5/8" @ 209'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE

ADDRESS: P.O BOX 333, ATTICA, KS 67009 LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: RUSSEL MEYER

COMPANY NAME: BISON PRODUCTION COMPANY PHONE: _____

WERE: 5 1/2" AT 4406' CIBP AT 2960' AND 5 SACKS
OH 4406' - 4415' 35 SACKS AT 1400'
35 SACKS AT 950'
CIRCULATE 280' - 0'

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { _____ } PART { } NONE { _____ }

COMPLETED: HOUR: 12:00 DAY: 13 MONTH: 3 YEAR: 1997

ACTUAL PLUGGING REPORT: THE CASING WAS PARTED AT 3034'. A CIBP WAS SET AT 2960' AND CAPPED WITH 5 SACKS OF CEMENT. THE CASING WAS RECOVERED FROM 2500' AND PULLED TO 1436' WHERE 35 SACKS OF CEMENT WAS SPOTTED. CASING PULLED TO 946' WHERE 35 SACKS OF CEMENT WAS SPOTTED. CASING PULLED TO 280' WHERE CEMENT WAS CIRCULATED TO SURFACE. REMAINING CASING PULLED AND CEMENT TOPPED OFF.

REMARKS: 60/40 POZ 4% GEL ALLIED CEMENT

INVOICED

DATE 4-17-97

INV. NO. 47964

RECEIVED
KANSAS CORPORATION COMMISSION

APR 16 1997

CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

[Signature]
STEVE VAM GIESON

FORM CP-2/3

REV. 3/90

DW