

To: 1 040758 6-8
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket # D-19,225

NW NE NE, SEC. 3, T 31 S, R 10 W/EX
4770 feet from S section line
810 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Lawrence "M" Well # 1

Operator: Marathon Oil Company

County Barber

Name & Address P.O. Box 689

Well Total Depth 4518 146.83 feet

Oklahoma City, OK 73101-0689

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 279

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1:15 p.m. Day: 8 Month: 6 Year: 1993

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling (phone) 316-624-7455

work: 5 1/2" at 4110' w/150 sx cement, 4" liner from 3983-4504' w/50 sx cement,

PBTD 4480', Perfs at 3750-85', CIBP at 3900'

1st plug pump 20 sx cement to 3600'.

2nd plug pump 50 sx cement at 520',

3rd plug pump 40 sx cement at 300', 4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 8 Month: 6 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 100 lbs. hulls and 20 sx common cement. Stopped plug at 3650'.

Loaded hole with drilling mud and spotted plugs through casing while laying down pipe:

2nd plug at 600' with 50 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 3514' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 7-8-93

INV. NO. 38056

Signed Steve Middleton
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1993

CONSERVATION DIVISION
WICHITA, KANSAS