

1 080306

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C NE SW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,948 0000

1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Bertha Well # 1

Operator: Hummon Corporation
Name & Address 400 One Main Place
Wichita, KS 67202

County Barber 158.02

Well Total Depth 4862 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 226 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P. O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: noon Day: 14 Month: January Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" set at 4861' PBTD 4837' Perfs at 4759-4762'

1st plug sand back to 4710' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 100 sx cement.

Plugging Proposal Received by J. H. Metz
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 pm Day: 14 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4710' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 100 sx cement.

STATE CORPORATION COMMISSION

IAN 23 1985

Maximum pressure 600 psi and shut in 300 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 3410' 5 1/2" casing. Cemented by Buie
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

Signed J. H. Metz
(TECHNICIAN)