

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-20139-00-00
Spot: SESE Sec/Twnshp/Rge: 27-31S-9W
660 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: ROBINSON Well Number: 1
County: HARPER Total Vertical Depth: 4397 feet

Operator License No.: 32433
Op Name: ONSHORE, L.L.C.
Address: 200 E. FIRST ST. STE 301
WICHITA, KS 67202

Production Casing Size: 4.5 feet: 4391 100 SX CMT
Surface Casing Size: 8.625 feet: 249 235 SX CMT

\$142.90

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/17/2003 3:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: DAVID PAULY Company: PAULY AND ASSOCIATES Phone: (316) 250-2045

Proposed Plugging Method: PER KCC RULES AND REGULATIONS.

RECEIVED
KCC DISTRICT #2
APR 22 2003
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 04/17/2003 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:


A CIBP WAS SET AT 4320' TO COVER THE PERFS. THE CIBP WAS CAPPED WITH 2 SKS OF CEMENT. THE CASING WAS RECOVERED FROM 3400', AND PULLED FROM THE WELLBORE. TUBING WAS RUN TO 1300', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE TUBING WAS PULLED TO 700', WHERE 35 SKS OF CEMENT WAS SPOTTED. THE TUBING WAS PULLED TO 300', WHERE CEMENT WAS CIRCULATED TO SURFACE.

Remarks: ALLIED CEMENTING 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INITIALS

DATE 4-30-03

WELL NO. 2003061480