

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-20763-00-00  
Spot: SE Sec/Twnshp/Rge: 8-21S-20W  
1172 feet from S Section Line, 1288 feet from E Section Line  
Lease Name: STEFFEN A Well #: 1-8  
County: PAWNEE Total Vertical Depth: 2360 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2264		WITH 2 SX CMT
PROD	4.5	2360	0	WITH 125 SX CMT
SURF	7	960		WITH 800 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/05/2015 10:30 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 2264' WITH 2 SX CMT. PERFORATE AT 1300' & CIRCULATE CMT TO TOP OF SURFACE PIPE THROUGH CASING BOTH INSIDE & BACKSIDE OF CASING.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/06/2015 10:00 AM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 2264' WITH 2 SX CMT. PERFORATE AT 1300' PUMPED 500 SX CMT, DID NOT CIRCULATE. RAN OUT OF CMT. 2/6/15: TOC @ 230'. RUN TBG TO 212' & PUMPED 25 SX CMT. CIRCULATED TO SURFACE. TIED ONTO BACKSIDE & PRESSURED UP TO 500#.

Perfs:

Top	Bot	Thru	Comments
2314	2324		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: TBG

*2/25/15 ckm*

District: 01

Signed Robert Dickerson

(TECHNICIAN)

RECEIVED  
FEB 11 2015  
KCC DODGE CITY

KCC WICHITA  
FEB 19 2015  
RECEIVED

*SP*