

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-20855-00-01  
Spot: S2SENE Sec/Twnshp/Rge: 21-20S-19W  
2935 feet from S Section Line, 586 feet from E Section Line  
Lease Name: FOX Well #: 1  
County: PAWNEE Total Vertical Depth: 4316 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2258		WITH 2 SX CMT
CIBP		2353		
PROD	5.5	4314	0	WITH 150 SX CMT
SURF	8.625	497		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/09/2015 2:30 PM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 2258' & 2 SX CMT. PERFORATE AT 1400' & CIRCULATE CMT TO SURFACE IN & OUT OF 5 1/2".

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/10/2015 10:00 AM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 2258' WITH 2 SX CMT. PERFORATE AT 1400' & RUN TBG TO 1400'. CIRCULATE 5 1/2" CASING TO SURFACE WITH 250 SX CMT. PULLED TBG OUT. PUMPED DOWN 5 1/2" CASING WITH 75 SX CMT & DISPLACED CMT TO 600'. SHUT IN WITH 500 PSI. TAGGED TOC @ 596'. PERFORATE AT 550' & CIRCULATE CMT TO SURFACE ON BACKSIDE OF CASING WITH 150 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2308	2338		

KCC WICHITA  
FEB 20 2015  
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

2/25/15 CKM

District: 01

RECEIVED  
FEB 18 2015  
KCC DODGE CITY

Signed Robert Dickerson  
(TECHNICIAN)

ST