

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-21211-00-00  
Spot: S2SE Sec/Twnshp/Rge: 10-21S-20W  
618 feet from S Section Line, 1326 feet from E Section Line  
Lease Name: REIDERER Well #: 2-10  
County: PAWNEE Total Vertical Depth: 2390 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2186		WITH 2 SX CMT
PROD	4.5	2388	0	WITH 200 SX CMT
SURF	7	950		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/09/2015 12:30 PM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROELUM Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 2186' WITH 2 SX CMT. PERFORATE AT 1300' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/09/2015 1:10 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 2186' WITH 2 SX CMT. CANNOT PERFORATE CASING BECAUSE BACKSIDE WAS SQUEEZED. RAN TBG TO 1300' & CIRCULATED CMT TO SURFACE WITH 100 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2308	2318		
2236	2264		

KCC WICHITA  
FEB 20 2015  
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

2/25/15 CKM

District: 01

Signed Robert Dickerson  
(TECHNICIAN)

RECEIVED  
FEB 16 2015  
KCC DODGE CITY

SA