

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-21700-00-00
Spot: NWNESESW Sec/Twnshp/Rge: 32-20S-20W
1221 feet from S Section Line, 2295 feet from W Section Line
Lease Name: ARMSTRONG B Well #: 3
County: PAWNEE Total Vertical Depth: 4440 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2594		WITH 2 SX CMT
CIBP		4342		
PROD	5.5	4436	0	WITH 150 SX CMT
SURF	8.625	434		WITH 325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/14/2015 11:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: BRANDON Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 2594' WITH 2 SX CMT. PERFORATE AT 1400' & CIRCULATE CMT TO SURFACE IN & OUT OF 5 1/2" CASING.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 01/30/2015 12:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 2594' WITH 2 SX CMT. PERFORATED AT 1400' & PUMPED 400 SX CMT. HAD CIRCULATION BUT NO CEMENT TO SURFACE. DISPLACED BELOW SURFACE CASING WITH 12 BBL & SHUT IN. 1/30/15: TAGGED CMT AT 74' IN THE 5 1/2" X 8 5/8" ANNULUS. FILLED WITH 20 SX CMT. RAN TBG TO 495' & FILLED WITH 50 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4356	4358		
4342	4346		
4334	4336		
4324	4330		
2644	2656		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: TBG

2/25/15 CKM

District: 01

Signed Larry Adams PERT II
(TECHNICIAN)

RECEIVED
FEB 10 2015
KCC DODGE CITY

KCC WICHITA
FEB 19 2015
RECEIVED

[Signature]