

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-35191-00-00
Spot: NWSESE Sec/Twnshp/Rge: 10-17S-17W
956 feet from S Section Line, 959 feet from E Section Line
Lease Name: RAU Well #: 1
County: RUSH Total Vertical Depth: 3600 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3000		WITH 2 SX CMT
PROD	4.5	3599	0	WITH 275 SX CMT
SURF	8.625	217		WITH 135 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/12/2015 11:30 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: CIBP @ 3000' WITH 2 SX CMT. PERFORATE AT 1190' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/13/2015 3:20 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 3000' WITH 2 SX CMT. PERFORATE AT 1190'. PUMP DOWN 4 1/2" CASING WITH 140 SX CMT. DID NOT CIRCULATE.. DISPLACED CMT TO 600' & SHUT IN WITH 900 PSI. 2/13/15: PERFORATED AT 550' & PUMPED 325 SX CMT AT 400 PSI. DID NOT CIRCULATE. DISPLACED CMT TO 300'. TOC @ 300'. PERFORATED AT 250'. PUMPED WATER & PRESSURED TO 800 PSI. PUMPED 25 SX CMT DOWN CASING AT 800 PSI. SHUT IN AT 1000 PSI. TIED ONTO BACKSIDE & PUMPED 15 SX CMT AT 300 PSI. SHUT IN AT 300 PSI.

Perfs:

Top	Bot	Thru	Comments
3319	3404		
3032	3041		

KCC WICHITA
FEB 20 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

CKM 2/25/15

District: 01

Signed Robert Dickerson
(TECHNICIAN)

RECEIVED
FEB 18 2015
KCC DODGE CITY

[Handwritten Signature]