

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-21253-00-00
Spot: S2NWNWSW Sec/Twnshp/Rge: 32-15S-10W
2010 feet from S Section Line, 330 feet from W Section Line
Lease Name: VACEK Well #: 32-1
County: ELLSWORTH Total Vertical Depth: 3279 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: PO BOX 329
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	2890		
PROD	5.5	3233		220 SX
SURF	8.625	328		180 SX
T1	2.875	3240		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/12/2015 10:00 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: JOE ROH Company: BENNETT & SCHULTE OIL CO. Phone: (785) 483-2721

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 02/12/2015 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SET CIBP @ 2890' AND CAP WITH 2 SX'S CEMENT.
PERFORATE AT 1300', 950', AND 380'. RUN TUBING TO 1300' AND PUMP 2 SX'S GEL
FOLLOWED BY 35 SX'S CEMENT. PULL TUBING UP 500' AND WAIT 1.5 HOURS.
RUN TUBING BACK DOWN AND TAG CEMENT AT 1307'. PULL TUBING TO 950'
AND PUMP 35 SX'S CEMENT, PULL TUBING TO 3580' AND CIRCUALTE CEMENT TO
SURFACE. PULL TUBING OUT AND TOP OFF. CONNECT ON TO SURFACE
CASING - PRESSURED RIGHT UP.

Perfs:

Top	Bot	Thru	Comments
3232	3241		
2942	2950		

Received
KANSAS CORPORATION COMMISSION
FEB 23 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. PIONEER SVC. PERF #47923. QUALITY WELL TICKET #1387.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

2/25/15 CKM