

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-20628-00-00
Spot: SWNENENE Sec/Twnshp/Rge: 29-24S-16W
425 feet from N Section Line, 407 feet from E Section Line
Lease Name: JONES Well #: 1-29
County: EDWARDS Total Vertical Depth: 4435 feet

Operator License No.: 34716
Op Name: BREITENBACH FAMILY FARMS LLC
Address: 4900 JOHNSON DR.
ROELAND PK, KS 66205

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4428	1246	WITH 175 SX CMT
SURF	8.625	249		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/17/2015 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT TO BOTTOM. PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ROBERT DICKERSON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2015 12:30 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

LEFT IN HOLE: RIPPER & CABLE BETWEEN 2200' & 1500'. PUMP DOWN 4 1/2" CASING WITH 25 SX CMT & 200# HULLS. SHUT IN WITH 700 PSI. TAGGED TOC @ 4000'. 1ST PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4304	4308		

KCC WICHITA
FEB 20 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

2/25/15 *CPM*

District: 01

Signed *Robert Dickerson*
(TECHNICIAN)

RECEIVED
FEB 18 2015
KCC DODGE CITY *MR*

SR