

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-093-20341-00-00
Spot: NESW Sec/Twnshp/Rge: 13-26S-35W
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: CITIZENS BLDG AND LOAN Well #: A-2
County: KEARNY Total Vertical Depth: 5220 feet

Operator License No.: 34997
Op Name: CASILLAS PETROLEUM CORP
Address: 401 S. BOSTON AVE, SUITE 2400
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4900		WITH 2 SX CMT
DVT		3079		WITH 500 SX CMT
PROD	5.5	5214	0	WITH 750 SX CMT
SURF	8.625	804		WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/30/2015 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: CHRIS Company: CASILLAS PETROLEUM Phone: (918) 582-5310

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2015 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:
CIBP @ 4900' WITH 2 SX CMT. PUMP 75 SX CMT WITH 250# HULLS AT 3691'. PUMP 20 SX CMT AT 1815'. CIRCULATED. TOOH WITH TBG. TEST CASING TO 600#. HOLDING. PERFORATE AT 830'. INJECTION RATE 1 1/2 BPM @ 600#. PUMP 150 SX CMT (70 SX CMT OUT PERFS) @ 1100 PSI WITH NO CIRCULATION TO SURFACE. PUMP 30 SX CMT DOWN THE ANNULUS TO 1200 PSI.

Perfs:

Top	Bot	Thru	Comments
5064	5071		
4964	4972		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Ken Jehlik (TECHNICIAN)

2/25/15 CCM

RECEIVED
FEB 10 2015
KCC DODGE CITY

KCC WICHITA
FEB 19 2015
RECEIVED

ST