

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-22333-00-00  
Spot: W2E2NENE Sec/Twnshp/Rge: 6-34S-13W  
4619 feet from S Section Line, 563 feet from E Section Line  
Lease Name: OTT B Well #: 3-6  
County: BARBER Total Vertical Depth: 5080 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4780		WITH 2 SX CMT
PROD	5.5	5061	2245	WITH 125 SX CMT
SURF	8.625	413		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/02/2015 12:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4780' WITH 2 SX CMT. PLUG AT 850' WITH 10 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/02/2015 1:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4780' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 864' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 463' WITH 50 SX CMT. 3RD PLUG AT 61' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4922	4940		
4831	4858		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Steve Pfeifer  
(TECHNICIAN)

2/25/15 CKM

RECEIVED  
FEB 13 2015  
KCC DODGE CITY

KCC WICHITA  
FEB 19 2015  
RECEIVED

SP