

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-22521-00-00  
Spot: S2NESWNE Sec/Twnshp/Rge: 6-34S-13W  
1860 feet from N Section Line, 1650 feet from E Section Line  
Lease Name: OTT B Well #: 4-6  
County: BARBER Total Vertical Depth: 5200 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4812		WITH 2 SX CMT
PROD	5.5	5197	3353	WITH 310 SX CMT
SURF	8.625	430		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/03/2015 2:00 PM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4800' & 2 SX CMT. PLUG AT 850' WITH 10 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/04/2015 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4812' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 874' WITH 15 SX GEL & 50 SX CMT. NO RETURNS. 2ND PLUG AT 468' WITH 10 SX GEL & 50 SX CMT. NO RETURNS. SDON TO LET CMT SET. 2/4/15: TAG TOC @ 500'. SPOTTED 50 SX CMT AT 468'. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4862	4892		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

*2/25/15 ckm*

District: 01

Signed *Stephen J. Pfeifer*  
(TECHNICIAN)

RECEIVED  
FEB 13 2015  
KCC DODGE CITY *AP*

KCC WICHITA  
FEB 19 2015  
RECEIVED