

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-30263-00-00
Spot: N2N2 Sec/Twnshp/Rge: 1-35S-14W
330 feet from N Section Line, 2640 feet from W Section Line
Lease Name: MORROW A Well #: 1-1
County: BARBER Total Vertical Depth: 4925 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4774		WITH 2 SX CMT
PROD	5.5	4925	2970	WITH 200 SX CMT
SURF	8.625	384		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/11/2015 11:45 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 4774' WITH 2 SX CMT. PLUG AT 609' WITH 10 SX GEL & 50 SX CMT. PLUG AT 435' WITH 50 SX CMT. PLUG AT 58' WITH 35 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 02/11/2015 1:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4774' WITH 2 SX CMT. 1ST PLUG AT 609' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 435' WITH 50 SX CMT. 3RD PLUG AT 58' WITH 35 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4824	4839		


Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

2/25/15 CKM

District: 01

Signed 
(TECHNICIAN)

RECEIVED
FEB 13 2015
KCC DODGE CITY 

KCC WICHITA
FEB 19 2015
RECEIVED 