

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-00199-00-00
Spot: NE Sec/Twnshp/Rge: 35-21S-33W
1320 feet from N Section Line, 1320 feet from E Section Line
Lease Name: GANO Well #: 1-35
County: FINNEY Total Vertical Depth: 2690 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1998		WITH 2 SX CMT
PROD	5.5	2689	0	WITH 300 SX CMT
SURF	8.625	304		WITH 225 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/02/2015 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 150 SX CMT WITH 300# HULLS. DISPLACE TO 1100'. TEST CASING TO 700#. RUN CBL FROM 1125' TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2015 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TBG STUCK IN HOLE. CUT TBG OFF AT 2000'. LEFT 642' OF 2 3/8" TBG IN WELL. SET CIBP @ 1998' WITH 2 SX CMT. LOAD CASING & TEST TO 500#. RUN CBL FROM 1998' TO 0'. TOC BEHIND 5 1/2" AT 1580'. PERFORATE AT 1130'. INJECTION RATE 1 1/2 BPM @ 1000 PSI. PUMP 40 SX CMT, 50# HULLS THEN 40 SX CMT. DISPLACE TO 700' @ 400# LEAVING 40 SX CMT OUTSIDE OF THE CASING AND 40 SX CMT INSIDE THE CASING. PERFORATE AT 330'. CIRCULATE CMT TO SURFACE WITH 100 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2642	2668		


Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

2/25/15 CKM

District: 01

Signed



(TECHNICIAN)

RECEIVED
FEB 11 2015
KCC DODGE CITY

KCC WICHITA
FEB 19 2015
RECEIVED

