

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-00252-00-00
Spot: SE Sec/Twnshp/Rge: 24-22S-32W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: LEWIS Well #: 1-24
County: FINNEY Total Vertical Depth: 2775 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2774	0	WITH 300 SX CMT
SURF	8.625	506		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/04/2015 1:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 200# HULLS & 140 SX CMT. DISPLACE TO 1300' +/- . TEST CASING TO 700#. RUN CBL FROM 1300' TO TOC. RUN TBG AND/OR PERFS AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2015 6:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 140 SX CMT DOWN 5 1/2" CASING. DISPLACE TO 1330' & PRESSURE TEST CASING TO 600#. RUN CBL FROM 1640' TO 950'. TOC BEHIND 5 1/2" CASING IS AT 1500'. PERFORATE AT 1300'. INJECTION RATE 2 1/2 BPM AT 800#. PUMP 40 SX CMT, 50# HULLS THEN 40 SX CMT. DISPLACE TO 800' @ 1000#, LEAVING 40 SX CMT INSIDE THE CASING AND 40 SX CMT OUTSIDE THE CASING. PERFORATE AT 520'. CIRCULATE CMT TO SURFACE WITH 40 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2684	2692		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

2/25/15 CKM

SP

RECEIVED
FEB 11 2015
KCC DODGE CITY

KCC WICHITA
FEB 19 2015
RECEIVED