

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21197-00-00
Spot: SW Sec/Twnshp/Rge: 28-21S-32W
1334 feet from S Section Line, 4024 feet from E Section Line
Lease Name: CRAIG Well #: 2-28
County: FINNEY Total Vertical Depth: 2848 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2620		
PROD	4.5	2837	0	WITH 710 SX CMT
SURF	8.625	328		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/03/2015 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: DUMP 2 SX CMT ON CIBP @ 2620'. RUN TBG TO 1700' & SPOT 30 SX CMT WITH 200# HULLS. PULL TBG TO 1200' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2015 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

(7/1/93: COILED TBG WAS RAN DOWN THE 4 1/2" X 8 5/8" ANNULUS TO 412' & CMT WAS CIRCULATED TO SURFACE.) CIBP @ 2620'. RUN TBG TO 2030' & SPOT 10 SX CMT. PULL TBG TO 1681' & SPOT 30 SX CMT WITH 200# HULLS. PULL TBG TO 1202' & CIRCULATE CMT TO SURFACE WITH 75 SX CMT. TOOH WITH TBG & TOP OFF 4 1/2" CASING WITH 10 SX CMT. ATTEMPT TO PUMP DOWN 4 1/2" X 8 5/8" ANNULUS AT 2500#. COULD NOT.

Perfs:

Top	Bot	Thru	Comments
2667	2677		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

2/25/15 CKM

District: 01

Signed

[Signature]
(TECHNICIAN)

RECEIVED
FEB 11 2015
KCC DODGE CITY [Signature]

KCC WICHITA
FEB 19 2015
RECEIVED