

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-21035-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 34-29S-34W
313 feet from S Section Line, 5005 feet from E Section Line
Lease Name: MLP CLAWSON Well #: 1-34
County: HASKELL Total Vertical Depth: 5650 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2650		WITH 2 SX CMT
CIBP		5386		WITH 2 SX CMT.
PC		2975		
PROD	5.5	5644	0	WITH 445 SX CMT
SURF	8.625	1770		WITH 650 SX CMT

Well Type: EOR UIC Docket No: E28039.5 Date/Time to Plug: 02/17/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 5386' WITH 2 SX CMT. SET CIBP @ 2650' WITH 2 SX CMT. RUN CBL TO DETERMINE PLUGGING ORDERS.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2015 2:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5386' WITH 2 SX CMT. SET CIBP @ 2650' WITH 2 SX CMT. CBL SHOWED TOC @ 300'. 1ST PLUG AT 1805' WITH 25 SX CMT. 2ND PLUG AT 654' WITH 83 SX CMT TO 0'. CHECK BACKSIDE WITH 8 SX CMT TO 500 PSI.

Perfs:

Top	Bot	Thru	Comments
5436	5446		

Received
KANSAS CORPORATION COMMISSION
FEB 23 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
FEB 19 2015
KCC DODGE CITY

Signed [Signature] 2/25/15 CKM
(TECHNICIAN)
cc: uic