

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-10184-00-00
Spot: SWNW Sec/Twnshp/Rge: 2-35S-32W
1980 feet from N Section Line, 660 feet from W Section Line
Lease Name: WHITE Well #: 1
County: SEWARD Total Vertical Depth: 6293 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5870		WITH 2 SX CMT
COND	13.375	625		WITH 350 SX CMT
DVT		876		WITH 219 SX CMT
PROD	5.5	6013	1947	WITH 250 SX CMT
SURF	9.625	2496		WITH 594 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/05/2015 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DENNIS FLANN Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 5870' WITH 2 SX CMT. PLUG AT 2530' WITH 30 SX CMT. PLUG AT 1500' WITH 10 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 60' WITH 25 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/05/2015 12:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5870' WITH 2 SX CMT. 1ST PLUG AT 2530' WITH 30 SX CMT. 2ND PLUG AT 1496' WITH 10 SX GEL & 70 SX CMT. 3RD PLUG AT 552' WITH 50 SX CMT. 4TH PLUG AT 64' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5920	5939		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED COMMON CEMENT BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
FEB 11 2015
KCC DODGE CITY

Signed

[Signature]
KCC WICHITA (TECHNICIAN)

FEB 19 2015
RECEIVED

2/25/15 CKM
[Signature]