

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-30013-00-00
Spot: SWSW Sec/Twnshp/Rge: 18-34S-36W
642 feet from S Section Line, 643 feet from W Section Line
Lease Name: FOSTER (STEVENS) Well #: 2-18
County: STEVENS Total Vertical Depth: 6900 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2230		WITH 2 SX CMT
CIBP		6245		
PROD	4.5	6455	1824	WITH 350 SX CMT
SURF	8.625	1771		WITH 625 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/30/2015 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 6256' WITH 2 SX CMT. PLUG AT 1800' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2015 11:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

TAG EXISTING CIBP @ 6245'. SET CIBP @ 2230' WITH 2 SX CMT OVER CASING
LEAKS AT 2335'. 1ST PLUG AT 1796' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT
599' WITH 40 SX CMT. 3RD PLUG AT 63' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6306	6314		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Kenny Sullivan 2/25/15 CKM
(TECHNICIAN)

RECEIVED
FEB 10 2015
KCC DODGE CITY

KCC WICHITA
FEB 19 2015
RECEIVED