

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-23333-00-00  
Spot: SWNENENE Sec/Twnshp/Rge: 8-35S-11W  
400 feet from N Section Line, 419 feet from E Section Line  
Lease Name: MOTT Well #: 1  
County: BARBER Total Vertical Depth: 5452 feet

Operator License No.: 33235  
Op Name: CHIEFTAIN OIL CO., INC.  
Address: 101 S. 5TH ST. PO BOX 124  
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4750		WITH 2 SX CMT
PROD	5.5	5437	2700	WITH 225 SX CMT
SURF	8.625	331		WITH 275 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/27/2015 9:00 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4750' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: NONE  
Date/Time Plugging Completed: 01/27/2015 11:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 4750' WITH 2 SX CMT. 1ST PLUG AT 598' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 378' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4824	4838		
4800	4820		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Larry Harris PERT H  
(TECHNICIAN)

RECEIVED  
FEB 10 2015  
KCC DODGE CITY

KCC WICHITA  
FEB 19 2015  
RECEIVED

Form CP-2/3