

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-19009-00-01
Spot: NWSENW Sec/Twnshp/Rge: 36-27S-15W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: BARNES Well #: 1
County: PRATT Total Vertical Depth: 4471 feet

Operator License No.: 3532
Op Name: CMX, INC.
Address: 1700 N WATERFRONT PKWY BLDG 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4418		WITH 2 SX CMT
PROD	4.5	4545	375	WITH 250 SX
SURF	8.625	310		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/17/2015 2:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTEIN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4420' WITH 2 SX CMT. PLUG AT 1140' WITH 15 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL
Date/Time Plugging Completed: 02/18/2015 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4418' WITH 2 SX CMT. 2/17/15: UNABLE TO FREE UP CASING. WELL WAS SQUEEZED WITH 50 SX CMT FROM 763-795'. 1ST PLUG AT RIPPED HOLE IN CASING AT 930'. PUMPED DOWN 4 1/2" CASING WITH 55 SX CMT. DISPLACED CMT TO 440'. 2/18/15: TAGGED TOC AT 463'. RIPPED CASING AT 375'. LAY DOWN CASING & RUN TBG INTO 369'. 2ND PLUG SPOT 135 SX CMT FROM 369' TO SURFACE. CMT DID CIRCULATE.

Perfs:

Top	Bot	Thru	Comments
4470	4472		

Received
KANSAS CORPORATION COMMISSION
FEB 23 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed [Signature] 2/25/15 CKM
(TECHNICIAN)
SP

RECEIVED
FEB 19 2015
KCC DODGE CITY