

15-077-76206-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 28 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name SeRoBee Drlg Co Inc & Shaffer Oil Co  
Complete Address 256 N Topeka Wichita, KS  
Lease Name Newberry Well No. 2  
Location 50' W/NE NE/NE Sec. 35 Twp. 31 Rge. 9 (E) (W) W  
County Harper Total Depth 4433  
Abandoned Oil Well X Gas Well ✓ Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Clarke Corporation  
Address Box 187 Medicine Lodge, KS License No. 583  
Operation Completed: Hour 10:00 AM Day 27 Month 2 Year 1975

The above well was plugged as follows:

218 ft 8 5/8 surface cement circulated. 4427 ft 5 1/2 long string cemented  
with 100 sacks. Open hole. Sand to 4400 ft, 5 sacks cement with  
bailer. Pulled 3700 ft 5 1/2. Set 10 ft rock bridge at 200 ft, 25  
sacks cement. Mud to 40 ft, plug, 1 sack hulls, 10 sacks cement  
to surface.

I hereby certify that the above well was plugged as herein stated.

Signed:                     

Well Plugging Supervisor

INVOICED

DATE 3/5/75

INV. NO. 924-W