

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1965
8-30-65
CONSERVATION DIVISION
Wichita, Kansas

15-077-00132-4300

Operator's Full Name Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name Campbell Well No. # 2

Location SW SW NE Sec. 36 Twp. 31 Rge. 9 (E) (W)W

County Harper Total Depth 4460'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 10:00AM Day 28th Month August Year 1965

The Above well was plugged as follows:

120' of 8 5/8" surface pipe, cemented with 150 sacks. 4460' of 5 1/2" long
string, cemented with 100 sacks. Plug back to 3990'. Top perforation
3940'. Bottom of the hole was sanded to 3930', and cemented with 5 sacks.
3430' of 5 1/2" long string was recovered from the hole. Hole was bailed
down to 200', bridge plug and rock bridge from 200' to 190', and cemented
with 10 sacks. Hole was filled with mud to 120', rock bridge from 120' to
110', and cemented with 15 sacks. Hole was filled with mud to 40', rock
bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 8/30/65

INV. NO. 1721-W