

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-007-20486-0000 of this well)

Operator's Full Name Texas Oil & Gas Corp.

Complete Address 200 W. Douglas, Suite 300, Wichita, Ks. 67202

Lease Name Rucker Well No. 1

Location App. C N/2 SW NW Sec. 20 Twp. 31s Rge. 10 (E) (W) X

County Barber Total Depth 4574

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Clarke Corp.

Address 107 W. Fowler, Medicine Lodge, Ks. 67104 License No. 583

Operation Completed: Hour 11:30 Am Day 18 Month 2 Year 1980

The above well was plugged as follows:

257' 8 5/8" casing w/250 sax cement. 4 1/2" casing set at 4568' w/100
sax cement. Plug back to 4549'-Pref. at 4540' to 4546'-CIBP at 4535'-
Top pref., at 4510' to 4514'-Sand back to 4489'-Top sand w/4 sax mixed
cement w/dump bailer. Pull 3800' casing. Allied mixed & pumped 5 sax
hulls-20 sax gel-100 sax 50/50 posmix cement w/4% gel & 3% cc to
top of casing. Shut in w/"0" pressure.

RECEIVED
STATE CORPORATION COMMISSION

FEB 20 1980

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED
DATE 2-22-80
INV. NO. 1573W