

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

JUN 9 1975

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Walters Drlg Co 15-007-16685-0000

Complete Address 400 Insurance Bldg Wichita, KS

Lease Name Inslee C Well No. 1

Location C NE/NW Sec. 20 Twp 31 Rge. 10 (E) (W)

County Barber Total Depth 4500

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 11:00 AM Day 5 Month 6 Year 1975

The above well was plugged as follows:
227 ft 8 5/8 surface cement circulated. 4499 ft 5 1/2 long string
cemented with 150 sacks. Top perf. 4442 ft. Sand to 4400 ft, 5 sacks
cement with bailer. Pulled 2200 ft 5 1/2. Set 10 ft rock bridge at
300 ft. Fill hole with 6 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6/9/75
INV. NO. 1455-W