

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mull Drlg Co 15-077-00970-0000

Complete Address Box 328 Attica, KS

Lease Name Antrim Well No. 1

Location NW/NW/NW Sec. 25 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4370

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Rockhold Engineering Inc

Address Box 698 Great Bend, KS License No. 670

Operation Completed: Hour 10:00 AM Day 10 Month 6 Year 1974

The above well was plugged as follows:

200 ft 8 5/8 surface cemented with 200 sacks. 4369 ft 4 1/2 long string
cemented with 100 sacks. Top perf. 4354 ft. Sand to 4300 ft, 4 sacks
cement with bailer. Pulled 3000 ft 4 1/2. Set 10 ft rock bridge at
250 ft. Fill hole with 5 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: Russell Liberton
Well Plugging Supervisor

INVOICED

DATE 6/12/74
INV. NO. 9289-W