

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1974

CONSERVATION DIVISION
Wichita, Kansas

15-677-10105-0000

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Robin Supply Corporation

Complete Address 1322 E. 50th Tulsa, OK

Lease Name Antrim Well No. 1

Location SW/NE/SE Sec. 25 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4396

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 11:00 AM Day 24 Month 1 Year 1974

The above well was plugged as follows:

220 ft 8 5/8 surface cemented with 200 sacks. 4395 ft 5 1/2 long string
cemented with 150 sacks. Open hole. Sand to 4000 ft. 5 sacks cement
with bailer. Pulled 2900 ft 5 1/2. Set 10 ft rock bridge at 360 ft.
Fill hole with 6 yds redmix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 1/30/74

INV. NO. 8456-W