

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

FEB 24 1964

15-077-00898-0000

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Mull Drilling Co., Inc.

Complete Address: 1625 Wichita Plaza, Wichita, Kansas

Lease Name Jacobs Well No. # B-4

Location C SW NE Sec. ²⁶23 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4423

Abandoned Oil Well X Gas Well Input Well SWD. Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:00AM Day 22nd Month Feb. Year 1964

The Above well was plugged as follows:

200' of 8 5/8" surface pipe, cemented with 160 sacks. 4422' of 4 1/2" long
string, cemented with 125 sacks. Bottom of hole was sanded to 4410', and
cemented with 3 sacks. Hole was bailed down to 225', plug was set at 225',
with 10' rock bridge, and cemented with 25 sacks, bringing the cement to
145' in the surface pipe. Hole was filled with mud to 40', 10' rock brid-
ge, and cemented with 10 sacks to base cellar.
3700' of 4 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/27/64
INV. NO. 8692-u