

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-077-10177-0000

Well Plugging Authority,
issued December 12, 1966

RECEIVED
JAN 23 1967
KANSAS STATE CORPORATION COMMISSION
CONSERVATION DIVISION

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: Box 562, Great Bend, Kansas

Lease Name Rall "C" Well No. # 1

Location NW NW SW Sec. 26 Twp. 31 Rge. 9 (E) (W) W

County Harper Total Depth 4504'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 2:00PM Day 20th Month Jan. Year 1967

The Above well was plugged as follows:

221' of 8 5/8" surface pipe, cemented with 150 sacks. 4502' of 5 1/2" long
string, cemented with 100 sacks. Plug back T.D. 4467'. Top perferation
4416'. Bottom of the hole was sanded to 4400', and cemented with 5 sacks,
through the dump bailer. 3640' of 5 1/2" long string was recovered from the
hole. Fluid in the hole was bailed down to 220', bridge plug and rock
bridge from 220' to 210', and cemented with 25 sacks. Hole was filled with
mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to
the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/23/67
INV. NO. 4648-w