

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19190-00-00

Spot: S2NWNW

Sec/Twnshp/Rge: 27-25S-5E

4174 feet from S Section Line, 4589 feet from E Section Line

Lease Name: MILLS

Well #: 7-A

County: BUTLER

Total Vertical Depth: 2453 feet

Operator License No.: 33192

Op Name: CROWN ENERGY COMPANY

Address: 1117 N.W. 24TH ST.

OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

PROD	4.5	880		50 SX
------	-----	-----	--	-------

SURF	8.625	70		150 SX
------	-------	----	--	--------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/21/2014 8:00 AM

Plug Co. License No.: 34928

Plug Co. Name: IRON HORSE WELL SERVICE LLC

Proposal Rcvd. from: DALLAS FLOWERS

Company: CROWN ENERGY CO.

Phone: (316) 323-3869

Proposed
Plugging
Method:

AS PER KCC RULES & REGS/ CIBP @ 700', CIRCUALTE 250'-0'.

Plugging Proposal Received By: B. J. HOPE

WitnessType: NONE

Date/Time Plugging Completed: 11/21/2014 5:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 810', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL, .75# POLYFLAKE 2% CC & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 460'. TESTED CASING @ 200#, HELD OK. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 250'-251' (4 HOLES). SWEDGED INTO 4.5" CASING, ESTABLISHED CIRCULATION, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 189 SXS 60/40 POZMIX 4% GEL 1% CC TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 5:00 PM 11/21/2014. CEMENT TICKET #48471.

Perfs:

Top	Bot	Thru	Comments
840	867	CSG	

Received
KANSAS CORPORATION COMMISSION
FEB 23 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

2/25/15 CLKM

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

✓