

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19193-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 27-25S-5E
4096 feet from S Section Line, 3316 feet from E Section Line
Lease Name: MILLS Well #: 2-B
County: BUTLER Total Vertical Depth: 2464 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2449		50 SX
SURF	15	88		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2014 8:00 AM
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY CO. Phone: (316) 323-3869

Proposed
Plugging
Method:

AS PER KCC RULES & REGS/ SAND @ 2399 W/7 SXS / PERF 250' & CIRC TO SURFACE.

Plugging Proposal Received By: B. J. HOPE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2403'. CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL, .75# POLYFLAKE 3% CC & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 2109'. RIH W/ TBG @ 658', CONSOLIDATED WELL SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS 60/40 POZMIX 4% GEL, 3% CC & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 564'. TESTED CASING @ 200#, HELD OK. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 250'-251' (4 HOLES). SWEDGED INTO 7" CASING, ESTABLISHED CIRCULATION, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 160 SXS 60/40 POZMIX 4% GEL 1% CC TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 5:00 PM 11/19/2014. CEMENT TICKET #48505.

Perfs:

Top	Bot	Thru	Comments
2450	2464	CSG	

Received
KANSAS CORPORATION COMMISSION
FEB 23 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

CKM 2/25/15

1/34