

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-19199-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 27-25S-5E  
1705 feet from N Section Line, 560 feet from W Section Line  
Lease Name: MILLS Well #: 58  
County: BUTLER Total Vertical Depth: 645 feet

Operator License No.: 33192  
Op Name: CROWN ENERGY COMPANY  
Address: 1117 N.W. 24TH ST.  
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	605		100 SX
SURF	7	62		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/19/2014 8:00 AM  
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC  
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY CO. Phone: (316) 323-3869

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND @ 550 W/ 4 SXS/ PERF 250' & CIRC TO SURFACE.

Plugging Proposal Received By: B. J. HOPE WitnessType: NONE  
Date/Time Plugging Completed: 11/20/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/3 7/8" BIT & 2 3/8" TBG CIRCULATING BRIDGES FROM 90'- 550'. W/TBG @ 550', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL, .75# POLY FLAKE 2% CC & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 413'. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 250'-251'- (4 HOLES). RIH W/TBG @ 250', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 135 SXS 60/40 POZMIX 4% GEL 1% CC TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 5:00 PM 11/20/2014. CEMENT TICKET #48468.

Perfs:

Top	Bot	Thru	Comments
605	645	OH	

Received  
KANSAS CORPORATION COMMISSION  
**FEB 23 2015**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)

2/25/15 ckm