

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40306-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 27-25S-5E
380 feet from N Section Line, 360 feet from W Section Line
Lease Name: MILLS Well #: 3 LCS
County: BUTLER Total Vertical Depth: 695 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	693		0 SX
SURF	8.625	0		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2014 8:00 AM
Plug Co. License No.: 34928 Plug Co. Name: IRON HORSE WELL SERVICE LLC
Proposal Rcvd. from: DALLAS FLOWERS Company: CROWN ENERGY COMPANY Phone: (316) 323-3869

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND @ 643 W/ 4 SXS/ PERF 250' & CIRC TO SURFACE.

Plugging Proposal Received By: B. J. HOPE WitnessType: NONE
Date/Time Plugging Completed: 11/21/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG @ 600', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL. 75# POLYFLAKE 2% CC & DISPLACED IN CASING. TAGGED CEMENT PLUG @ 426'. TESTED CASING @ 200#. HELD OK. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 250'-251' (4 HOLES). SWEDGED INTO 4.5" CASING, ESTABLISHED CIRCULATION, CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 178 SXS 60/40 POZMIX 4% GEL 1% CC TO SURFACE. CEMENT CIRCUALTED. PLUG DOWN 5:00 PM 11/21/2014. CEMENT TICKET #48469.

Perfs:

Top	Bot	Thru	Comments
693	695	OH	

Received
KANSAS CORPORATION COMMISSION
FEB 23 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

2/25/15 CKM