

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-20331-00-00
Spot: NENESW Sec/Twnshp/Rge: 26-24S-31W
2610 feet from S Section Line, 2610 feet from W Section Line
Lease Name: DECHANT Well #: 1
County: FINNEY Total Vertical Depth: 2725 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2750	587	WITH 125 SX CMT
SURF	8.625	524		WITH 400 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/30/2015 9:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 02/03/2015 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1/30/15: PUMP 25 SX CMT WITH 200# HULLS TO 2699'. AFTER 4 HOURS TAG TOC @ 2312'. PRESSURE TEST CASING TO 800#. HELD. BLEW A HOLE IN CASING AT 1125'. ESTABLISHED INJECTION RATE THROUGH HOLE DOWN 4 1/2" CASING.
2/2/15: SPOTTED 80 SX CMT 1/2 IN AND 1/2 OUT OF THE 4 1/2" CASING AT 1125'.
PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2689	2699		


Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

2/25/15 CKM

District: 01


Signed



(TECHNICIAN)

RECEIVED
FEB 11 2015
KCC DODGE CITY

KCC WICHITA
FEB 19 2015
RECEIVED



Form CP-2/3