

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-21769-00-00
Spot: NW Sec/Twnshp/Rge: 25-16S-17W
1158 feet from N Section Line, 1282 feet from W Section Line
Lease Name: STREMEL Well #: 1-A
County: RUSH Total Vertical Depth: 2200 feet

Operator License No.: 34811
Op Name: KANSAS PETROLEUM RESOURCES, LL
Address: 200 E. 1ST STREET, STE 307
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1900		WITH 2 SX CMT
PROD	4.5	2130	0	WITH 400 SX CMT
SURF	8.625	869		WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/12/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GEORGE UTLEY Company: KANSAS PETROLEUM RESOURCE Phone: (214) 924-2588

Proposed Plugging Method: SET CIBP @ 1900' WITH 2 SX CMT. PERFORATE AT 1170' & CIRCULATE CMT TO SURFACE UP BACKSIDE OF CASING.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/12/2015 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 1900' WITH 2 SX CMT. PERFORATE AT 1165'. TIED ONTO CASING & PUMPED 325 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2086	2092		
2012	2024		
1978	1984		
1957	1972		
1956	2200		

KCC WICHITA
FEB 20 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

2/25/15 CKM

District: 01

Signed Michael J. Maier
(TECHNICIAN)

RECEIVED
FEB 17 2015
KCC DODGE CITY