

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-047-21540-00-00
Spot: SWNESE Sec/Twnshp/Rge: 2-26S-18W
2297 feet from S Section Line, 331 feet from E Section Line
Lease Name: WILDHORSE FARMS Well #: 1
County: EDWARDS Total Vertical Depth: 4799 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>6236</u>	PROD	4.5	3364	2190	WITH 125 SX CMT
Op Name: <u>MTM PETROLEUM, INC.</u>	SURF	8.625	279		WITH 250 SX CMT
Address: <u>2370 SOUTH STATE ROAD 14 PO BOX KINGMAN, KS 67068</u>					

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/12/2015 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT TO 3160'. PLUG AT 1240' WITH 15 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ROBERT DICKERSON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/12/2015 11:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

PUMP 200# HULLS & 25 SX CMT TO 3160'. 1ST PLUG AT 1240' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3210	3216		

KCC WICHITA
FEB 20 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

2/25/15 CKM

District: 01

Signed Larry Harris (TECHNICIAN)

RECEIVED
FEB 17 2015
KCC DODGE CITY

[Handwritten Signature]