

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25519-00-00
Spot: SESWNENE Sec/Twnshp/Rge: 7-17S-24W
1212 feet from N Section Line, 813 feet from E Section Line
Lease Name: TILLITSON Well #: 1-7
County: NESS Total Vertical Depth: 4550 feet

Operator License No.: <u>5144</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>MULL DRILLING COMPANY, INC.</u>	CIBP		4425		
Address: <u>1700 N WATERFRONT PKWY BLDG 12</u>	PC	5.5	1807		WITH 160 SX CMT
<u>WICHITA, KS 67206</u>	PROD	5.5	4537	0	WITH 150 SX CMT
	SURF	8.625	224		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/28/2015 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: KYLE RANDA Company: MULL DRILLING Phone: (785) 798-3306

Proposed Plugging Method: PUMP 50 SX CMT & 200# HULLS, SPACE TO 1800' THEN CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/28/2015 10:10 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

TIED ONTO CASING & PUMPED 50 SX CMT & 200# HULLS, SPACER TO 1800'.
PUMPED 175 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN WITH 500#. TIED
ONTO BACKSIDE & PUMPED 30 SX CMT. PRESSURED TO 400# & HELD.

Perfs:

Top	Bot	Thru	Comments
4438	4448		
4364	4367		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED OIL

Plugged through: CSG

2/25/15 CKM

District: 01

Signed

Michael J. Maier
(TECHNICIAN)

RECEIVED
FEB 10 2015
KCC DODGE CITY

KCC WICHITA
FEB 19 2015
RECEIVED