

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-093-20194-00-00
Spot: NESWSWSE Sec/Twnshp/Rge: 33-25S-36W
350 feet from S Section Line, 2290 feet from E Section Line
Lease Name: LEE Well #: 7-4
County: KEARNY Total Vertical Depth: 5203 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		3144		WITH 550 SX CMT
PROD	5.5	5194	0	WITH 350 SX CMT
SURF	8.625	912		WITH 600 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE HAYES Company: OIL PRODUCERS Phone: (620) 546-4456

Proposed
Plugging
Method:

PUMP 80 SX CMT WITH 300# HULLS AT 3800'. PUMP 175 SX FROM 1800' TO 0'. USE 75 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK
Date/Time Plugging Completed: 02/02/2015 1:00 PM

Witness Type: COMPLETE (100%)
KCC Agent: KEN JEHLIK

Actual Plugging Report:

LEFT IN HOLE TOP TO BOTTOM: 9 1/2 JOINTS 2 3/8" TBG, TOP VIP PACKER, 300' OF 3" TBG, BOTTOM VIP PACKER AND 31 JOINTS OF 2 3/8" TBG. TOP OF FISH @ 3835'. TWO ATTEMPTS TO FISH WERE UNSUCCESSFUL. PUMP 80 SX CMT WITH 300# HULLS AT 3800' TO 3000'. WELL CIRCULATED. PULL TBG TO 1797' & CIRCULATE CMT TO SURFACE WITH 165 SX CMT. TOOH WITH TBG. TOP OFF 5 1/2" WITH 50 SX CMT. PUMP 30 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
4970	4978		


Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

2/25/15 CKM

District: 01

Signed



(TECHNICIAN)


KCC WICHITA

FEB 19 2015

RECEIVED

RECEIVED
FEB 11 2015
KCC DODGE CITY





Form CP-2/3