

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-21321-00-00
Spot: SENESEW Sec/Twnshp/Rge: 21-31S-21W
2096 feet from S Section Line, 2660 feet from E Section Line
Lease Name: MOORE Well #: 21-11-8
County: CLARK Total Vertical Depth: 6417 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 124 N MAIN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	44		
PROD	5.5	5304	2190	WITH 350 SX CMT
SURF	8.625	673		WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/09/2015 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 35 SX CMT & 200# HULLS. PLUG AT 1100' WITH 10 SX GEL & 50 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 350' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/08/2015 12:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMP 200# HULLS & 35 SX CMT. PRESSURED TO 700#. 1ST PLUG AT 1110' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 710' WITH 50 SX CMT. 3RD PLUG AT 340' WITH 40 SX CMT. 4TH PLUG AT 38' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5151	5158		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

2/25/15 CKM

District: 01

Signed [Signature]
(TECHNICIAN)

KCC WICHITA
FEB 19 2015
RECEIVED

RECEIVED
FEB 16 2015
KCC DODGE CITY