

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20333-00-00
Spot: NWSESWNE Sec/Twnshp/Rge: 35-19S-29W
2038 feet from N Section Line, 1772 feet from E Section Line
Lease Name: DAVIS N Well #: 1
County: LANE Total Vertical Depth: 4700 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4450		
PROD	4.5	4698	0	WITH 175 SX CMT
SURF	8.625	306		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2015 8:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 214-0330

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 30 SX CMT & 200# HULLS. PULL TBG & PERFORATE AT 2200' & SPOT 50 SX CMT. PULL TBG & PERFORATE AT 1300' & PUMP 80 SX CMT OVER CASING VOLUME. IF NO CIRCULATION PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2015 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4380' & PUMP 30 SX CMT & 200# HULLS. PULL TBG & PERFORATE AT 2200'. RUN TBG TO 2230' & PUMP 50 SX COMMON CMT WITH 3% CC. WAIT 1 1/2 HOURS. PERFORATE AT 1300'. TIED ONTO CASING & PUMPED 135 SX CMT. DID NOT CIRCULATE. TIED ONTO BACKSIDE & PUMPED 100 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4470	4471		
4368	4373		
4358	4359		

KCC WICHITA
FEB 20 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

2/25/15 ckm

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
FEB 17 2015
KCC DODGE CITY