

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-20620-00-01
Spot: NWNESW Sec/Twnshp/Rge: 31-18S-23W
2076 feet from S Section Line, 3577 feet from E Section Line
Lease Name: SCHNIEPP Well #: 3
County: NESS Total Vertical Depth: 1313 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1306	0	WITH 350 SX CMT
SURF	8.625	206		WITH 150 SX CMT

Well Type: SWD UIC Docket No: D20264.0 Date/Time to Plug: 02/16/2015 1:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: ERIK HAGANS Company: VINCENT OIL CORPORATION Phone: (620) 388-5858

Proposed
Plugging
Method:

RUN TBG & CIRCULATE CMT & HULLS TO SURFACE. PULL TBG & TOP OFF. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/16/2015 2:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

COULDN'T GET PACKER OUT OF HOLE. WAS UNABLE TO GET THE PACKER BACK DOWN ANY DEEPER THAN 1072'. LAID THE TOP JOINT OF TBG DOWN. TBG @ 1052'. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURING TO 300#. TIED ONTO TBG & PUMPED 150 SX CMT WITH 200# HULLS, CIRCULATING CMT TO SURFACE INSIDE OF THE 5 1/2". PULLED TBG & TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
1004	1144		

KCC WICHITA
FEB 20 2015

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

2/25/15 ckm

District: 01

Signed E. Maier
(TECHNICIAN)

cc: UIC

RECEIVED
FEB 17 2015
KCC DODGE CITY

Form CP-2/3