

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-21545-00-00
Spot: NE Sec/Twnshp/Rge: 18-20S-23W
3928 feet from S Section Line, 1347 feet from E Section Line
Lease Name: DIETTERICH Well #: 1
County: NESS Total Vertical Depth: 4399 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 155 N MARKET STE 700
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4324 | | WITH 2 SX CMT |
| PROD | 4.5 | 4388 | 0 | WITH 100 SX CMT |
| SURF | 8.625 | 296 | | WITH 225 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/16/2015 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: ERIK HAGANS Company: VINCENT OIL CORPORATION Phone: (620) 388-5858

Proposed Plugging Method: CIBP 50' ABOVE PERFS & LOG.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/16/2015 10:00 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4324' WITH 2 SX CMT. LOADED HOLE WITH FLUID AND LOGGED 1700' TO SURFACE. FOUND CMT AT 1400' TO 300'. SWABBED CASING TO 1500'. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 250# BEFORE BLOWING CMT UP THE OUTSIDE OF THE 8 5/8". TIED ONTO 4 1/2" CASING & PUMPED 100 SX CMT. PRESSURED TO 200#.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4394 | 4399 | | |
| 4388 | 4394 | | |

KCC WICHITA
FEB 20 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

2/25/15 CKM

District: 01

Signed Eric Maclaren
(TECHNICIAN)

RECEIVED
FEB 17 2015
KCC DODGE CITY

SP