

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-22035-00-00  
Spot: E2NWSW Sec/Twnshp/Rge: 31-18S-23W  
2038 feet from S Section Line, 922 feet from W Section Line  
Lease Name: SCHNIEPP Well #: 2  
County: NESS Total Vertical Depth: 4300 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 155 N MARKET STE 700  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4120		WITH 2 SX CMT
PROD	5.5	4299	0	WITH 375 SX CMT
SURF	8.625	569		WITH 400 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/16/2015 11:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: ERIK HAGANS Company: VINCENT OIL CORPORATION Phone: (620) 388-5858

Proposed Plugging Method: CIBP 50' ABOVE PERFS WITH 2 SX CMT. RUN TBG TO 1500' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. USE 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/16/2015 12:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

\*\*TOP STAGE CEMENTED WITH 200 SX CMT. SQUEEZED CASING LEAKS @ 2015' & 362' WITH 100 SX CMT. CASING PRESSURED TO 650#.\*\* SET CIBP @ 4120' WITH 2 SX CMT. TIED ONTO BACKSIDE & PUMP 10 SX CMT. PRESSURED TO 500#. TIED ONTO 5 1/2" & PUMPED 150 SX CMT. PRESSURED TO 1000# WITH SLIGHT BLEED OFF. CMT FELL 160'. TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4246	4252		
4164	4167		


KCC WICHITA  
FEB 20 2015  
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

2/25/15 CKM

District: 01

Signed   
(TECHNICIAN)

RECEIVED  
FEB 17 2015  
KCC DODGE CITY 