

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-23193-00-02
Spot: NWNWNESE Sec/Twnshp/Rge: 28-33S-8E
2468 feet from S Section Line, 1101 feet from E Section Line
Lease Name: BURNETT Well #: 1
County: COWLEY Total Vertical Depth: 2400 feet

Operator License No.: 7775
Op Name: WILTON PETROLEUM, INC.
Address: PO BOX 391
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2399		40 SX
SURF	8.625	450		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2014 8:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE Phone: (620) 628-4723

Proposed Plugging Method: AS PER KCC RULES & REGS / 25 SXS ON BOTTOM, CIRCULATE 500'-0'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 12/09/2014 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

SANDED BACK WELL BACK @ 2274', DUMP BAILED 5 SXS CEMENT ON TOP OF SAND. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 500'-501' (4 SHOTS). SWEDGED INTO CASING, WELL WOULD NOT CIRCUALTE. RIH W/1" TBG ON INSIDE OF 5 1/2" CASING @ 515', CONSOLIDATED ESTABLISHED CIRCULATION, MIXED & PUMPED 54 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TBG. RIH ON BACKSIDE OF 5 1/2" CASING W/ 1" @ 315', CONSOLIDATED ESTABLISHED CIRCUALTION, MIXED & PUMPED 86 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. TOTAL OF 140 SXS TICKET #48434.

Perfs:

Top	Bot	Thru	Comments
2324	2336		CSG

Received
KANSAS CORPORATION COMMISSION
FEB 23 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: TA

Plugged through: TBG

2/25/2015 CKM

District: 02

Signed Duane Krueger
(TECHNICIAN)

JK